

The landowner is responsible for locating and staking all existing tile lines prior to commencing any construction. RRVCSA assumes no responsibility for damage to existing tile lines.

Minnesota specifications for conservation practices apply for all materials and construction work. These specifications are part of this


The Owner shall notify the Engineer and SWCD at least two (2) working days prior to the start of construction.

NOTE: Changes in the drawings or specifications must be authorized by the owner and the NRCS, RRVCSA, or SWCD representative with the proper approval authority.

The owner is responsible for obtaining land rights and local, state, and federal permits or other permission necessary to perform and maintain the practice.


Before start of construction, the owner(s) of any utilities involved must be notified. The excavator is responsible by state law for giving notice by calling "Gopher State One-Call" at (651) 454-0002 (twin cities metro area) or (800) 252-1166 (all other locations) at least 48 hours prior to any excavation.

GSOC Number



NOTE: HORIZONTAL/VERTICAL ACCURACY UNKNOWN HORIZONTAL DATUM: UTM ZONE 15 NORTH, NAD 1983 VERTICAL DATUM: NAVD 88, GEOID 18

Detail Plans for Sorvig LLP 468 Lined Waterway or Outlet Pennington County, Minnesota



<u>CO1</u>	NSTR	UCTIO	N (CERTI	FICATION
					standards No
	cted		· —	/00	

Certified by:

INDEX OF DRAWINGS						
Sheet Number	Title					
1	Cover Sheet and Quantities					
2	Plan View, Profiles, Typical Sections, Details, and Notes					

SUMMARY OF ESTIMATED QUANTITIES					
No.	Quantity	Unit	Item		
CS001	1	LUMP SUM	Mubilization		
CS005	1	LUMP SUM	Pollution Control		
CS002	1	LUMP SUM	Clearing and Grubbing		
CS021	136	CU YD	Excavation - Common, Waterway Shaping		
CS023	115	CU YD	Compacted Earthfill, Repair Erosion		
CS095	390	SQ YD	Geotextile, Geotex 701 or Equivalent		
CS061	95	CU YD	Random Riprap, MnDOT Class II		
CS006	1	LUMP SUM	Seeding and Mulching		

1. CV - Compacted Volume

(P) - Denotes a plan quantity with no additional compensation.

3. Geotextile Class 1 - Non Woven, shall be overlapped and anchored 18in. minimum along sides and 24in. minimum on the ends.

4. Seed and Mulch all disturbed areas.

I have reviewed and understand the plans and specifications and agree to complete the work accordingly. Failure to meet these plans and specifications may jeopardize any cost share applied for. I understand that it is my responsibility to secure all necessary permits and licenses, and to complete the work in accordance with all local, state, and federal laws. Modifications of these plans or specifications must be approved by the Engineer before installation. I assume responsibility for negotiations and agreements with the contractors.

COOPERATORS SIGNATURE

DATE

No.	Revision	Date	Ву	
			+	
				Sorvig LLP

COVER SHEET 468 Lined Waterway or Outlet

> Pennington Soil & Water Conservation District Drawn LAH Pennington County, Minnesota Checked LAH

1000'

Red River Valley Conservation Service Area 8/29/2022 Designed Logan Handyside 8/29/2022

1000'

Scale in Feet

2000'

9/30/2022

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the state of Minnesota.

License #55889

ile Name Eng. Job Class

Sheet 1 of 2

Date: 9/30/2022 Logan Handyside

BENCH MARK _ESCRIPTIONS

TBM #1 ELEV = 1008.00' TOP OF 24" CMP ON SOUTH SIDE OF 110TH ST. SW


NOTE: HORIZONTAL/VERTICAL ACCURACY UNKNOWN HORIZONTAL DATUM:

UTM ZONE 15 NORTH, NAD 1983 VERTICAL DATUM:


NAVD 88. GEOID 18

LEGEND

BENCH MARK. TEMPORARY CONTOUR CONTOUR. INDEX








TYPICAL RIPRAP DITCH SECTION

(Not to Scale)



TYPICAL DITCH SECTION

(Not to Scale)

- 1. Ditch Grading consists of shaping, repairing, and regrading existing eroded ditch section to proposed typical section and profile shown in the plans.
- Outside bend of ditch shall have riprap extend up the inslope an additional 2'. Place riprap around existing culvert outlet.
 Erosion control measures must be put in place to prevent sediment from moving downstream of the construction site until excavation operations are complete and ditch is stabilized.
- 4. Place Spoil where it will not interfere with surface water flow into the waterway.
- 5. Do not disturb road adjacent to project site.



36+50

No.	Revision	Date	Ву	
\vdash			-	
\vdash			+	ł
				Sorvia LLP

CONSTRUCTION PLAN 468 Lined Waterway or Outlet

> Pennington Soil & Water Conservation District Drawn LAH Pennington County, Minnesota Checked LAH

35+00

Red River Valley Conservation Service Area 8/29/2022 Designed Logan Handyside 8/29/2022

36+00

Sorvig Ditch

9/30/2022

35+50

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the state of Minnesota.

37+00

Signature: Date: 9/30/2022 License #55889 Logan Handyside

37+50

1000

37+75

File Name Sorvig.dug

Eng. Job Class Sheet 1 of 2